THROUGH FASTENER SYSTEM

MATERIALS

Stock Colors
29 ga. Painted Galvalume 4 sq x 105.00 = 420
****NON-Stock Colors ADD 20%**

Valley
29 ga. /24" Preformed Valley (10ft) ____ pc x 40.00 = ____
TARCO Ice Guard $10.00LF x ____ = ____

Drip Edge
Standard
26 ga. / 3"x 3" Eave Edge (10ft) 4 pc x 15 = 60
Over Lath
26 ga. /4.5"x 4.5" Eave Edge (10ft) ____ pc x 20 = ____

Hip & Ridge Cap
29 ga. /14" Ridge Cap (10ft) 3 pc x 27 = 81

Rake Edge
26 ga. Outside Corner (10ft) 4 pc x 21 = 48

Inside Closure Strip (Drip Edge)
IC (3ft) 17 pc x 5 = 85

Outside Closure Strip (Both sides ridge cap not hips)
*NON Vented Ridge
OC (3ft) 17 pc x 5 = 85
Vented Outside Closure (Both sides ridge vent @ cap)
VOC (3ft) ____ pc x 12 = ____

EMSEAL (Both sides hips and valleys)
EMSEAL (19LF/Roll) ____ Roll x 40 = ____

Repel Synthetic Underlayment
Summit 60 (10 sq Roll) .5 Rolls x 82.00 = 41

Wall Flashings
All Wall Flashings (10ft) ____ pc x 35.00 = ____

Transition Flashings
Coil Stock (26 ga) ____ pc x 36.00 = ____
1 Roll per Job add=$125.00

Touch Up Paint
1 Bottle per Job add=$12

Pipe Boots
1 ¼"-5" ____ pc x 26 = ____
5"-9" ____ pc x 66.00 = ____
10"-19" ____ pc x 166 = ____
Split Boot ____ x 50 = ____

Urethane Sealant
per Job 15.00
~~add=$40.00~~

Snow Rails (Garage Doors, Entry Ways, Side Walks)
Snow Rail 10' Long ____ pc x 40 = ____

Fasteners
1 ½" Wood Screws (90sq) 4 sq x 25.00 = 100
2" Wood Screw (2 bag/house) $107.00
On Hip Roof (4 bags/house) $214.00

2x4 Lath
2x4 Lath—10' ____ pc x 5.00 = ____
2x4 Lath—12' ____ pc x 7= ____
2x4 Lath—16' ____ pc x 9 = ____

Decking*
7/16" OSB ____ pc x $ = ____
***Call Lowes every 2 weeks for Price and add $2/Sheet**

Total Materials 935

INSTALL LABOR SCALE

	7/12	9/12	11/12	OVER
TO1	40	50	60	70

Additional Layers 10/Layer x ____=____
Sheeting 15/Sheet x ____= ____
1 X Sheeting ____x 2.00 = ____

	Up to 7/12	Up 9/12	Up to 11/12	Up to 12/12	over
METAL	$120	$130	$140	$150	discuss

LATH ____sqs. x $30 = ____
TO ____sqs. x ____ = ____
SHEET ____sqs. x $30 = ____
METAL 4 sqs. x 120 = 480

Chimney $200
Skylight $150

Cut in Box Vent= $10.00pc x ____pc =____

Total Labor ____

Miscellaneous

*Flat roof mat. & labor $550/sq (+lyrs or difficult = more $)

Total Misc. 100
ALWAYS ADD $100

Materials ~~& Labor & Misc~~ = 935
x **7%tax** = 66
Labor + 480
Dump Up TO 30sq =400 ____

Subtotal 1481

Total ÷ .65 % 2,378.73

Price per sq 570