Roofing, Windows, Siding, Gutters, & Insulation

Rich Roofing & Services

937 - 335 - Roof (7663)

PROPOSAL

567 E. STAUNTON RD.
Troy, OH. 45373
Ph. 937.335.ROOF (7663)
Fax 937.335.3285
www.richroofing.com

To:
Pastor Jeff Gephart
1509 West Main St
Troy, OH 45373

Job Name/No:
Location: SAME
Home:
Cell: (937) 339-0015
Work Phone:
Date: 3/19/2026

We hereby submit specifications and estimates for: **House Roof Replacement**

Emergency dry-in windstorm damaged areas.
Replace any missing or damaged vinyl siding on steeple.
Remove old roofing and haul 1 layer of asphalt.
Replace up to 2 sheets of decking. If more bad decking is found upon Tear-Off, it will be replaced at $3.50 per sq. ft
Install ice and water guard underlayment at drip eaves. Building Code
Install all new Synthetic Underlayment.
Install all new aluminum drip and rake edge trim.
Recover with Lifetime /dimensional shingles, (with *Scotchgard* Algae Protection), storm nailed (6 nails per shingle)
Install 2 new vent pipe collars.
All new Wall and Step flashings (.019 aluminum.) as needed.
Re-flash 1 chimney.
Remove and Replace 120 ft. of Shingle-Over Ridge Vent. Building Code
Clean-up and dispose all work-related debris.

5 Year Workmanship Warranty
Lifetime Manufacture Warranty
Authorization to place dumpster: In Driveway
Due to the amount of debris caused by tearing off a roof, we recommend you cover-up or remove any items in your attic

Rich Roofing and Exteriors has been voted The #1 Roofing Company for 14 consecutive years! Thank you!!
E-Z Financing Available

WE PROPOSE hereby to furnish material and labor-complete in accordance with these specifications for the sum of: **$ 28,410.73**
Payable as follows: ½ Down and Balance on Completion A 2% finance charge will be added to your bill if payment is not received within 5 days after the due date on your invoice. We accept Visa and MasterCard. Due to the amount of minimal vibration during the roofing procedure, Rich & Son's will not be responsible for any interior damage. We advise that all things be properly secured to walls, ceilings, and etc. All materials are guaranteed to be as specified. In the event that this contract is canceled after contractor purchases material, any and all materials must be paid for in full. All warranties void if not paid in full. All work to be completed in a workmanlike manner according to standard practices. Any alteration or deviation from above specifications involving extra cost will be executed only upon written orders, and will become an extra charge over and above the estimate. Any additional disposal cost due to type of material, will be homeowners responsibility to pay for. All agreements contingent upon strikes, accidents or delays beyond our control. Weather and working conditions to be determined by Rich & Sons, Inc. Owner to carry fire, tornado, and other necessary insurance. Our workers are fully covered by Workmen's Compensation Insurance. **This quote is good for 15 days.**

ACCEPTANCE OF PROPOSAL-The prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. You have 3 business days to rescind. If you rescind after the 3rd day, a 3% restocking fee will apply. Payment will be made as outlined above. Please sign and return one copy.

Representative J.L.C. Date: 3/19/2026 Payment terms: 1/2 down balance due upon completion

Authorized signature _____ Date 3/26/2026

For office use only: **Management approval:** _____ **Date:** _____