Sherriff Goslin Roofing

2115 Valley St
Dayton, OH 45404
Dayton@SherriffGoslin.com
(937)-237-9313

Client:	Micah Strateger	Home:	(937) 502-5511
Property:	7500 Sweet Potato Ridge Rd Brookville , OH 45309		
Operator:	DAYTON		
Estimator:	Alex Reindel	Business:	(937) 237-9313
Position:	Office Manager	E-mail:	Areindel@SherriffGoslin.com
Company:	Sherriff Goslin Roofing		
Business:	2115 valley St Dayton, OH 45505		
Reference:	Jason Hadden	Business:	(937) 623-6371
Position:	Branch Manager	E-mail:	Jhadden@Sherriffgoslin.com
Company:	Sherriff Goslin Roofing		
Business:	2115 Valley St Dayton, OH 45404		

Type of Estimate:	Wind Damage		
Date Entered:	10/15/2024	Date Assigned:	10/15/2024
Price List:	OHDT8X_OCT24		
Labor Efficiency:	Restoration/Service/Remodel		
Estimate:	MICAH_STRATEGR		

Sherriff Goslin Roofing

2115 Valley St
Dayton, OH 45404
Dayton@SherriffGoslin.com
(937)-237-9313

MICAH_STRATEGR

Dwelling Roof

DESCRIPTION	QTY	REMOVE	REPLACE	TAX	TOTAL
1. Remove Laminated - comp. shingle rfg. - w/out felt	26.88 SQ	63.52	0.00	0.00	1,707.42
2. Laminated - comp. shingle rfg. - w/out felt	29.67 SQ	0.00	247.14	262.83	7,595.47
3. Additional layer of comp. shingles, remove (no haul off)	26.88 SQ	28.90	0.00	0.00	776.83
4. Roofing felt - synthetic underlayment - Standard grade	21.28 SQ	0.00	36.55	16.71	794.49
5. Ice & water barrier	560.00 SF	0.00	1.64	19.99	938.39
6. R&R Drip edge	248.00 LF	0.41	2.69	18.92	787.72
7. Asphalt starter - universal starter course	248.00 LF	0.00	1.99	10.42	503.94
Required on eaves and rakes					
8. R&R Flashing - pipe jack	3.00 EA	8.62	47.84	3.36	172.74
9. Step flashing	16.50 LF	0.00	10.00	2.24	167.24
Wall flashing above garage					
10. R&R Flashing, 14" wide	35.00 LF	0.72	4.58	4.97	190.47
Transition metal from roof to awning					
11. R&R Exhaust cap - through roof - up to 4"	2.00 EA	11.01	89.96	5.46	207.40
Currently is a turtle type roof vent and needs to be corrected					
12. R&R Continuous ridge vent - aluminum	84.00 LF	1.05	9.33	23.40	895.32
Totals: Dwelling Roof				368.30	14,737.43
Line Item Totals: MICAH_STRATEGR				**368.30**	**14,737.43**

Additional Charges	**Charge**
Post-Construction Clean-up	200.00
Additional Charges Total	**$200.00**

Sherriff Goslin Roofing

2115 Valley St
Dayton, OH 45404
Dayton@SherriffGoslin.com
(937)-237-9313

Summary

Line Item Total	14,369.13
Post-Construction Clean-up	200.00
Material Sales Tax	368.30
Replacement Cost Value	**$14,937.43**
Net Claim	**$14,937.43**

Alex Reindel
Office Manager