

Roofing, Windows, Siding, Gutters, & Insulation

PROPOSAL

567 E STAUNTON RD
Troy, OH. 45373
Ph. 937.335.ROOF (7663)
Fax 937.335.3285
www.richroofing.com

To:
Sam Lane
1159 South Main Street
West Milton, OH. 45383

Job Name/No:
Location: **SAME**
Cell: (937) 479-7156
Home Phone:
Work Phone:
Fax:
Date: 11-10 -21

We hereby submit specifications and estimates for: **Attic Insulation** (Area: Climate Zone 5)

1) Prep attic as needed.
2) Install 12 Attic Vent Baffles.
3) Install 12 inches of Blown Cellulose Insulation using Cap-Over Method. Resulting in 16 inches of insulation in attic.
   Approx. 47 R-Value as recommended for Climate Zone 5 in Ohio.
4) Remove incorrect dryer vent on roof and install Large Damper Dryer Vent.
5) Clean up and dispose of any work related debris.

Rich Roofing and Exteriors was voted #1 by Readers Choice Awards for our 12th straight year! THANK YOU!!

WE PROPOSE hereby to furnish material and labor-complete in accordance with these specifications for the sum of: **$ 2,558.37**
Payable as follows: ½ Down and Balance on Completion A 2% finance charge will be added to your bill if payment is not received within 5 days after the due date on your invoice. We accept Visa and MasterCard; however, if you choose this method of payment, **an additional 3%** will be added to the amount due. Due to the amount of minimal vibration during the roofing procedure, Rich & Son's will not be responsible for any interior damage. We advise that all things be properly secured to walls, ceilings, and etc. All materials are guaranteed to be as specified. In the event that this contract is canceled after contractor purchases material, any and all materials must be paid for in full. All warranties void if not paid in full. All work to be completed in a workmanlike manner according to standard practices. Any alteration or deviation from above specifications involving extra cost will be executed only upon written orders, and will become an extra charge over and above the estimate. All agreements contingent upon strikes, accidents or delays beyond our control. Owner to carry fire, tornado, and other necessary insurance. Our workers are fully covered by Workmen's Compensation Insurance. This quote is good for 15 days.

ACCEPTANCE OF PROPOSAL-The prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. You have 3 business days to rescind. If you rescind after the 3rd day, a 3% restocking fee will apply. Payment will be made as outlined above. Please sign and return one copy.

Representative W.R. Date 11-10-21 Payment terms ½ down balance on completion

Authorized signature Samuel A Lane Date 11/11/21

For office use only: **Management approval:**_____ **Date:**_____